



Laboratory Report

Date **17-March-2015**

Customer **Yintec**
**Unit 13C, Level 3, 35-37 Princes Highway, Engadine
NSW 2233**

Test No : **AZT0059.15.xls**



NATA Accredited Laboratory No : 15147

Azuma Design Pty Limited
38-44 Redfern Street, Wetherill Park, NSW 2164 Ph 02 9604 0255 E-Mail info@azumadesign.com.au

This document is issued in accordance with NATA's accreditation requirements.
Accredited for compliance with ISO/IEC 17025.
This document shall not be reproduced, except in full .

AZUMA DESIGN

TESTING LABORATORY REPORT

Test equipments

The test equipment and methods used in the above test comply with the requirements of AS 4420.1-6.

Test Specimen

See drawings at the end of this report.

Test Methods

The test sample was fixed into the rig as outlined in AS 4420.1.

Deflection Test

The test sample was subjected to both positive and negative pressure as prescribed in AS 4420.2. After the initial settling in of the unit at 50% of the required test pressure, the differential pressure was then applied slowly until the nominated design pressure was reached in positive. This process was then repeated for the negative.

Results of Test

Not tested

Observations

Nil

Operating Force Test

A force gauge was attached to the operating handle of the sash to determine the force required to set the sash in motion and thereafter to maintain motion as per AS 4420.3.

Force in Newtons

		Force in Newtons	
		Opening Force	Closing Force
Initiating Movement	Sash 1		
Sustaining Movement	Sash 1		
Initiating Movement	Sash 2		
Sustaining Movement	Sash 2		
Initiating Movement	Sash 3		
Sustaining Movement	Sash 3		

Results of test

Not tested

Observations

Nil

AZUMA DESIGN

TESTING LABORATORY REPORT

Air Infiltration Test

The test was first completely sealed as per AS 4420.4 to determine the air leakage of the test rig. It was then subjected to 75 Pa of both positive and negative pressure. Differential pressures were recorded. The test sample was then unsealed and subjected to 75 Pa of both positive and negative pressure. Differential pressures were recorded and air leakage then calculated. The actual leakage of the test sample was then determined.

Barometric pressure (Pbar):	1016		Air temperature (°C)	23
Max Pressure (Pa)	SEALED		UNSEALED	
	Positive (Pa)	Negative (Pa)	Positive (Pa)	Negative (Pa)
75	2	2	11	15

Test Pressure	Pressure Direction	Building / Window Type	Allowable leakage flow L/s m ²	Test results			
				Is ⁻¹ m ⁻² Positive	Is ⁻¹ m ⁻² Negative	Pos +	Neg -
75 Pa	+/-	Air conditioned	1.0	0.65	0.84	Passed	Passed
75 Pa	+	Non air conditioned	5.0	0.65	0.84	Passed	

Results of test

The test unit satisfied the requirement of AS 4420.4. The net flow readings are as per previous page:

Observations

Nil

AZUMA DESIGN

TESTING LABORATORY REPORT

WATER PENETRATION

Water was applied to the exterior of the test sample with no less than 0.05 ls-1 m-2 for a period of five minutes at zero pressure. After five minutes, a nominated pressure was applied for fifteen minutes as per AS 4420.5.

Maximum pressure (Pa) applied for 15 minutes (Nominated pressure)

1000

Results of test

The test unit satisfied the requirement of AS 4420.5 in positive pressure at the nominated design pressure.

Observations

Wet seal between sub sill and frame

ULTIMATE STRENGTH TEST

The test sample shall be subjected to a smoothly increasing differential pressure. The pressure shall be conducted in both a positive and negative direction as per AS 4420.6. The test pressure shall be

Max. pressure reached for 10 seconds	
Positive	Negative
5000	5000

Results of test :	Y or N
Dislodgement of any glass?	No
Dislodgement of a frame or any part of a frame?	No
Removal of alignment with or without its framing sash from a frame?	No
Loss of support of a frame such as when it is unstable in its opening in the building structure?	No
Failure of any sash, locking device, fasteners or supporting stay which would allow an opening light to come open?	No
The test unit satisfied the requirement of AS 4420.6.	

Observations

Nil